MSBA OPM Roundtable

Presentation Panel on Project and Commissioning Closeout

Case Study from Marathon Elementary School, Hopkinton

February 28, 2019



One Edgewater Drive, Suite 204 | Norwood, MA 02062 508.589.5061 | www.compasspminc.com

AGENDA

- **Team Introduction**
- Schedule Management
- Design Considerations
- Training
- Maximize Assets
 - **Post Completion**
 - Q&A

MARATHON ELEMENTARY SCHOOL Project Panel





Planning Architecture Interior Design





BUILDING ENCLOSURE

SCHEDULE MANAGEMENT

- Project Team Focused Approach to Scheduling
- Utilize Early Trade Packages to Establish Momentum Across Trades
- Using Individual Trade Schedules to Propel Lean Construction, Commissioning, LEED & Training
- Full Schedule Buy-In from Trade Contractors
- Schedule Focused on "the Brain of the Building" (i.e Mechanical Room)
- Finished two months ahead of schedule inclusive of four classroom addition

- Cooperation of Trade Contractors allowed the added building to fit into schedule and budget seamlessly
- Successful Building Turnover Starts Early in Construction Phase
- Run Transition Process Parallel with FFE Procurement Schedule
- Outline Owner Transition Process
- Quantify Building Contents
- Attic Stock Considerations

148	GMP Development	78 days	Tue 8/23/16	Thu 12/8/16
149	Early Site & Foundation Packages Bidding	21 days	Tue 8/23/16	Tue 9/20/16 1
150	Early Steel Package Bidding	15 days	Thu 9/29/16	Wed 10/19/16 1
151	HESBC Review / Approve Early Trade Bid Award	3 days	Wed 9/21/16	Frl 9/23/16 1
152	Print & Distribute Bidding Documents	2 days	Mon 10/17/16	Tue 10/18/16 1
153	Advertise Trade Contractors	1 day	Wed 10/19/16	Wed 10/19/16 1
154	Subcontractor Bidding	15 days	Thu 10/20/16	Wed 11/9/161
155	CM GMP Development	20 days	Thu 10/20/16	Wed 11/16/161
156	Review & Scoping of CM GMP	5 days	Thu 11/17/16	Wed 11/23/161
157	HESBC Review / Approve Contract Award	5 days	Thu 11/24/16	Wed 11/30/161
158	Award Contract to CM - Notice to Proceed	1 day	Thu 12/1/16	Thu 12/1/16 1
159	Execute CM GMP Contract Amendment	5 days	Frl 12/2/16	Thu 12/8/16 1

DESIGN CONSIDERATIONS

- LEED v4 Flush-Out Criteria
- Used Option 1, Path 1, Flush-Out Before Occupancy
- Designer Matrix for all AHU Equipment and Building Space Requirements
- The Resulting Flush-Out Period was 16 Days - required to occur when construction ends and all interior finishes are installed





- The Mechanical Contractor provided a Flush-Out Data Log via Closeout Submittal
- Flush-out Data included: average space temperature, relative humidity, outside air flow and the air handling unit's outside air damper position
- Scheduled Commissioning of Building Systems after Flush Out


TRAINING Essential to Success of Team on Project

DRA Architects Implementation:

- Identify Facility Dept. Needs, Skill Set and Knowledge for Training
- Identify Pertinent Parties for Training and Provide List to Owner
- Include a Training Summary Spec. in the Front End

Colantonio Implementation:

- Consolidate Training Outline as Part of the Submittal Process
- Very Thorough Training Follow-Thru and Scheduling
- List Video Recording Requirements for Continuity of Standards



MAXIMIZE ASSETS

Efficiency of CxA involvement:

- Envelope Field Testing requirements identified in design phase for feedback.
- CxA included on Procore distribution of Submittals, Meeting Minutes & Field Reports by AE team
- Scheduled field visits based on up to date info & communication with Compass
- Deficiency tracking achieved via Procore with <u>PHOTOS</u> following discussion in field with OPM & CM
- MEP CX: Scheduling site visits for equipment startups, functional testing and 3rd Party TAB requires significant coordination
- OPM & CM ensured the prefunctional checklists were complete with system operations complete by trade contractors prior to our visit



MAXIMIZE ASSETS

- Tracked the Commissioning Corrective Action Log Items Through Observations Tool in Procore
- Items Added as Observations, Assigned to Subcontractor for Corrective Action
- Procore Sends the Individual Notification that an Observation in their Court has been Created.
- A Reasonable Due Date is Set for the Subcontractor to Correct issue Noted on the Observation.

- When Corrective Actions Completed, Subcontractor Changes status to "Ready For Review"
- CM & CxA Notified of Status Change to review response as acceptable or not
- If Not Acceptable, Status is Changed to "Initiated", Subcontracted to Review Comments and Resubmit.
- Provided WIFI in the construction
 Zone for subs



POST COMPLETION

- Establish flow for User request to determine if it is a warrantee item or Owner wish list.
- Staff requests, fill out form to be vetted through the Principal and/or Facilities Director to determine responsible party.
- Facility Director to distribute warrantee request to CM or wish list to OPM/SBC for consideration.
- CM schedules investigation or repair with subcontractors/vendors
- OPM works with School Staff or Designer to provide more information on wish list to present to SBC for action.

OWNER CHANGE REQUEST Hopkinton Marathon Elementary School INSTRUCTIONS: Please use this form to request a change or modification to the project. This form will be used only to document and track all Owner Change Requests. Submittal of this form does not guarantee that the change or modification will be approved and/or implemented. Change requests originating from the school staff/facility will first be submitted to the Superintendent of Schools for approval, and if approved, then submitted to the ESBC for approval and inclusion in the project. Approval by the School Department does not guarantee that a change request will be approved and/or implemented by the PBC. Owner Change Order Request # DATE OF REQUEST: 9/26/2017 Tim Persson REQUESTED BY: OMPLET ROOM # or LOCATION: fallway to Music Room C112 CHANGE OR MODIFICATION Add a lookable door or gate at the hallway leading to the muclo room whi DESCRIPTION: onnects to the cafeteria 100 School Facilities wishes for the option to look off the cafeteria space during REASON FOR CHANGE OR outside school rental events to keep renters out of the cafeteria and music room DEPT. spaces. This is an open hallway with stair that connects to the cafeteria space MODIFICATION: nd ultimately the stage if the sliding partition is not closed (CIRCLE ONE) RIORITY OF REQUEST: CHOOL CRITICAL HIGH LOW SCHOOL DEPARTMENT AUTHORIZATION (Superintendent Signature) (Date) SCHOOL DEPT. DECISION DESCRIPTION: DATE RECEIVED: 9/26/17 - at job meeting ASS TO PLETE SPEC, SECTION OR Doors & Hardware OMPASS CATEGORY: Sase condition is per plans & spec's. Order Magnitude Cost: \$5.000 This adds COM COMPASS COMMENTS: lexibility for building off hour management. The request is reasonable and we commend proceeding CPM PCO #: DRA - Proposal Request \$40 APPROVAL TO PRICE ESBC APPROVAL APPROVAL TO PROCEED (PLEASE CHECK ONE) NOT APPROVED Chairman or Vice Chair Signature

Marathon Elementary School Project Panel

THANK YOU!

OPEN DIALOGUE QUESTIONS & ANSWER